

Williamson 5/13/96
Alvarado 5-17-96
SN 5443

MAY 31 1996

In Reply Refer To: MS 5232

Tennessee Gas Pipeline Company
Attention: Mr. William M. Murray
Sugar Mill Point
1115 Regal Row
Houma, Louisiana 70360

Gentlemen:

Your letter dated March 12, 1996, requests approval to permanently abandon in place approximately 8,773 feet (1.66 miles) of 10-inch pipeline designated as Segment No. 5443, and to relinquish in its entirety, Right-of-Way Grant OCS-G 4040 associated therewith. The subject pipeline was used to transport gas from Platform B in Block A-336 to Platform A in Block A-343, High Island Area.

Pursuant to 30 CFR 250.4(b), approval is hereby granted to abandon the above described pipeline, and in accordance with 30 CFR 250.159(c), the requirement that the pipeline be removed is hereby waived. However, in the future, should it be determined that this abandoned pipeline constitutes a hazard to navigation or commercial fishing operations or unduly interferes with the other uses of the Outer Continental Shelf, Tennessee Gas Pipeline Company shall be required to remove it.

Pursuant to 30 CFR 250.150(b), the relinquishment of the right-of-way grant associated with the pipeline that is to be abandoned in place is hereby accepted effective March 15, 1996.

Sincerely,

(Orig. Sgd.) Kent E. Stauffer,

Donald C. Howard
Regional Supervisor
Field Operations

bcc: 1502-01 (P/L OCS-G 4040) w/enclosures (K.Faust) (MS 5232)
1502-01 (P/L OCS-G 4040) (microfilm) (MS 5033)
MS 5421
MS 5232 Carto

Williamson:amm:4/9/96:Tennessee.443

54040

ms 5443

on ms
6/6/96
B

Tennessee Gas Pipeline
Tenneco Energy
Sugar Mill Point
1115 Regal Row
Houma, Louisiana 70360
Tel 504 868 6785
Fax 504 868 1423

March 12, 1996



U.S. Department of the Interior
Minerals Management Service
Gulf of Mexico OCS Region
1201 Elmwood Park Boulevard
New Orleans, LA 70123-2394
Attention: Warren Williamson

Re: Permanent Abandonment and Relinquishment
of Pipeline Right of Way, OCS-G 4040, Seg.
No. 5443, High Island Block A-336-B Line


Dear Warren:

In accordance with Title 30 CFR Part 250, Subpart J, 250.156 and 250.164,
Tennessee Gas Pipeline Company hereby requests approval to permanently abandon and
relinquish approximately 1.66 miles of ten inch (10") pipeline in the High Island Area,
Offshore Texas.

The temporary cessation of the above pipeline was approved on April 10, 1995.
Tennessee Gas Pipeline Company hereby requests approval to relinquish the pipeline right of
way associated with this abandonment. TGP is requesting this permanent abandonment and
relinquishment based on the fact that there is no future use for this pipeline. This line has
been abandoned as proposed since April 1995.

If you should require any additional information regarding this matter, please call this
office.

Sincerely,


B. J. Chaney, Supervisor Rights
of Way as Agent and Attorney-in-Fact

KJC:kjc

cc: M. Taylor
P. Craft
P. Alexis

L. Rosales
File

Both ends
cut, capped &
buried as
outlined
in "out" letter of 3/17/95!

Patton 3-21-95

5N5443

In Reply Refer To: MS 5232

APR 10 1995

Tennessee Gas Pipeline Company
Attention: Mr. B. J. Chaney
Sugar Mill Point
1115 Regal Row
Houma, Louisiana 70360

Gentlemen:

Pursuant to the authority granted by 30 CFR 250.150(b), your request dated March 17, 1995, for modification of pipeline Right-of-Way OCS-G 4040 to allow for the temporary cessation of operation of pipeline Segment No. 5443 is hereby approved, subject to the following conditions:

1. The annual rental required by 30 CFR 250.159(c) (2) shall continue to be due and payable in December of each calendar year.

2. Tennessee Gas Pipeline Company shall, upon receipt of the necessary documentations which are required by the Federal Energy Regulatory Commission under Tennessee Gas Pipeline Company's blanket abandonment authorization, file an application to permanently abandon the subject pipeline and relinquish the right-of-way grant.

Sincerely,

(Orig. Sgd.) Kent E. Stauffer

Donald C. Howard
Regional Supervisor
Field Operations

bcc: 1502-01 (P/L OCS-G 4040) w/orig application (MS 5232)
1502-01 (P/L OCS-G 4040) w/cy of application (MS 5033)
MS 5232 Carto w/cy of location plat

FPatton:amm:3/21/95:Tennessee.443

5440

on msp
4/1/95
B

Tennessee Gas Pipeline

A Tenneco Company

Sugar Mill Point
1115 Regal Row
Houma, Louisiana 70360
(504) 868-6785



March 17, 1995

U.S. Department of the Interior
Minerals Management Service
Gulf of Mexico OCS Region
1201 Elmwood Park Boulevard
New Orleans, LA 70123-2394

Attention: Mike Conner



Re: Temporary abandonment of 8" natural
gas pipeline, High Island Block
A-336B Line, OCS-G 4040, Segment
No. 5443

Dear Mike:

In accordance with Title 30 CFR Part 250, Subpart J, 250.156, Tennessee Gas Pipeline Company hereby requests approval to temporarily abandon the above referenced pipeline in the High Island Area, Gulf of Mexico, Offshore Texas.

This pipeline extended from Tenneco Oil Company's High Island Block A-336-B platform to H.I.O.S.'s High Island Block A-343-A platform. The procedure which was used to abandon this facility is attached hereto.

Upon receipt of the necessary documentation, i.e., P & A reports, etc., which are required by FERC under TGP's blanket abandonment authorization, TGP will file to permanently abandon the above pipeline.


The line was purged with seawater to remove any materials which may have been harmful to the environment prior to abandonment.

Also, enclosed are three copies of Drawings which have been red-marked to show the completed work.

Page 2
March 17, 1995

If you should require any additional information regarding this matter, please call this office.

Sincerely,


B. J. Chaney, Supervisor
Rights of Way as Agent
and Attorney-in-Fact

BJC/KJC:kjc

Enclosures

cc: Marty Taylor
O. O. Jones
L. Rosales
G. Benoit
File

3-10-95 pjc

ABANDONMENT PROCEDURE
High Island A-336
Completed June 1983

1. Mobilize equipment to Tenneco Oil's High Island A-336-A platform and close main line Valve No. 823X-1602.
2. Install 8" Poly pig in pig trap.
3. Launch and run pig with high pressure water.
(9,463 ft. of 8.625" O. D. x .406 W. T. Pipe = 23,300 gallons.)
4. When pig reaches trap at H.I.O.S. High Island A-343-A platform, close main line valve 823X-1601.
5. Bleed water pressure from line.
6. Cut 8" pipeline sub-sea at base of risers at stations 4+50.7 and 91+52.6 (water depth approx. 235 ft.)
7. Install 8" foreman plugs in ends of abandoned pipeline.
8. Jet down ends of 8" pipeline and ensure they have 3 ft. of cover.
9. At High Island A-343-A, remove meter station, platform piping and riser from H.I.O.S. platform. Install 16" blind flange and 6" blind flange on H.I.O.S. piping.
10. At High Island A-336-A, remove meter station, platform piping and riser from Tenneco Oil platform. (Tenneco Oil to relocate and re-use platform decks)

TAX
DISTRICT
DATA

OWNERSHIP & LINE LIST NO.
H.I.O.S.-HIGH ISL.BLK.A-336A

BEST AVAILABLE COPY

UNITED STATES OF AMERICA
GULF OF MEXICO

GULF

M.P.
823X-1601
1.79

VAL. NO.
823X-1602
6.94+632

VAL. NO.
823X-1601
6.0+00

Abandon in Place

8" I.O.P. LINE NO. 823X-1600
(H.I.O.S.-HIGH ISLAND BLK.A-336A LINE)

DWG. TO F2-823X-1600-IB, IBI

DWG. TO F2-823X-1600-IA, IAI

TENNECO OIL COMPANY - H.I.O.S.
BLK.A-336A PLATFORM

X=3,616,415.25'
Y=131,231.07'
LAT. 28°06'05.57"N
LONG. 91°47'05.25"W


EXXON - H.I.O.S.
BLK.A-343A PLATFORM

X=3,694,520.97'
Y=131,646.72'
LAT. 28°05'20.20"N
LONG. 91°44'06.54"W


MEXICO

PLAN

SCALE: 1" = 400 FT.



PT.	BEARING & DISTANCE	LAMBERT COORDINATES
1	N 78°32'45"W - 692.85'	X=3,691,828.57' Y=131,616.72'
2	N 32°04'33"W - 374.93'	X=3,693,833.47' Y=131,810.00'
3	N 32°04'33"W - 374.93'	X=3,693,833.47' Y=131,810.00'
4	N 64°31'20"W - 1,023.02'	X=3,693,833.47' Y=131,810.00'
5	N 64°31'20"W - 1,023.02'	X=3,693,833.47' Y=131,810.00'
6	N 64°31'20"W - 1,023.02'	X=3,693,833.47' Y=131,810.00'
7	N 64°31'20"W - 1,023.02'	X=3,693,833.47' Y=131,810.00'
8	N 64°31'20"W - 1,023.02'	X=3,693,833.47' Y=131,810.00'
9	N 64°31'20"W - 1,023.02'	X=3,693,833.47' Y=131,810.00'
10	N 64°31'20"W - 1,023.02'	X=3,693,833.47' Y=131,810.00'
11	N 64°31'20"W - 1,023.02'	X=3,693,833.47' Y=131,810.00'
12	N 64°31'20"W - 1,023.02'	X=3,693,833.47' Y=131,810.00'
13	N 64°31'20"W - 1,023.02'	X=3,693,833.47' Y=131,810.00'
14	N 64°31'20"W - 1,023.02'	X=3,693,833.47' Y=131,810.00'
15	N 64°31'20"W - 1,023.02'	X=3,693,833.47' Y=131,810.00'




MATERIAL SUMMARY	
ITEM NO.	DESCRIPTION
1	ANODES, CYLINDRICAL 8"
2	PIPE, 8.625"O.D. X .406"W.T. GR.X-42 U.S. Steel
3	PIPE, 8.625"O.D. X .500"W.T. GR. B Youngstown
COATING "A" --- 3M Scotchote 218	

PROFILE

SCALE: HORIZ: 1"=400 FT.
VERT: 1"= 20 FT.


NOTE: CO-ORDINATES ON POINTS 1-15 WERE ESTABLISHED BY ODOM OFFSHORE SURVEY & ASSOC. SURVEY BEARINGS AND DISTANCES WERE CALCULATED USING THE LAMBERT GRID (LOUISIANA SOUTH ZONE) SYSTEM. THE ROUTE AS SHOWN MAY NOT NECESSARILY BE THE EXACT LOCATION OF THE PIPELINE.

DRAWING NO. 13862		REFERENCE DRAWINGS		Tennessee Gas Pipeline Company		H.I.O.S.- HIGH ISLAND BLK.A-336A LN.		APPROVED BY J.P. Halliwell	
PRELIM.		TITLE		Division of Tenneco Inc.		LINE NO. 823X-1600		ASST. CHIEF ENGINEER	
CONST.		TO F2-823X-1600-IA & IAI		Engineering Department		HIGH ISLAND AREA, GULF OF MEXICO		TENNESSEE GAS PIPELINE CO.	
FINAL		TO F2-823X-1600-IB & IBI		Houston, Texas		SCALE: SHOWN		TO F2-823X-1600-1	
LOG/NOTES						ISSUE DATES		VALVE SECTION ENTIRE LINE ON THIS SHEET	
						ORIGINAL 8-28-82			
						LAST 8-28-84			




H.I.O.S.-HIGH ISLAND BLK.
A-343 C.G. PLATFORM


PLAN
SCALE: 1/8"=1'-0"




SECTION "D-D"
SCALE: 3/8"=1'-0"




ROW A
SECTION "B-B"
SCALE: 1/8"=1'-0"



SECTION "C-C"
SCALE: 3/8"=1'-0"



ROW 2
SECTION "A-A"
SCALE: 3/8"=1'-0"



SECTION "E-E"
SCALE: 3/8"=1'-0"

ITEM NO.	DESCRIPTION
1	BOLTS, STUD, 5/8" X 4 1/2" ALLOY STEEL, W/2 HEX NUTS EACH
2	BOLTS, STUD, 7/8" X 6" ALLOY STEEL, W/2 HEX NUTS EACH
3	BOLTS, STUD, 3/4" X 5" ALLOY STEEL, W/2 HEX NUTS EACH
4	BOLTS, STUD, 1/2" X 3" ALLOY STEEL, W/2 HEX NUTS EACH
5	BOLTS, STUD, 1/2" X 10" ALLOY STEEL, W/2 HEX NUTS EACH
6	BUSHING, 2" X 1/2" F.S. SCREWED, 6000 P.S.I. WOG
7	CLAMP, PIPE AND BRACE, FOR 4" PIPE (COMPLETE)
8	CLAMP, RISER, FOR 8" PIPE
9	CLAMP, RISER, FOR 8" PIPE
10	CLAMP, RISER, FOR 8" PIPE
11	CLOSURE, HINGED, 10" A.N.S.I. 600 •
12	ELL, STRUT, 1" A.N.S.I. 3000 P.S.I. F.S. SCREWED
13	ELL, WELD, 2.375" O.D. X .218" W.T. GR. B 90° LR. (0.5' LG.)
14	ELL, WELD, 4.500" O.D. X .337" W.T. GR. B 90° LR. (1.0' LG.)
15	ELL, WELD, 8.625" O.D. X .500" W.T. GR. B 90° LR. (2.0' LG.)
16	ELL, WELD, 8.625" O.D. X .500" W.T. GR. B 42° 30' DEG. 301A. (4.0' LG.)
17	GASKET, 16" A.N.S.I. 600 • OVAL RING NO. 65
18	FLANGE, 2" A.N.S.I. 600 • RTJW ASTM A105
19	FLANGE, 4" A.N.S.I. 600 • RTJW ASTM A105
20	FLANGE, 6" A.N.S.I. 150 • RTJW
21	FLANGE, 8" A.N.S.I. 600 • RTJW ASTM A105
22	FLANGE, 8" A.N.S.I. 900 • RTJW ASTM A105
23	FLANGE, 8" A.N.S.I. 900 • SWIVEL RING RTJ ASTM A105
24	FLANGE, 16" A.N.S.I. 600 • RTJW GR. X-52
25	GASKET, 2" A.N.S.I. 600 • OVAL RING R23
26	GASKET, 8" A.N.S.I. 600 • OVAL RING R49
27	GASKET, 8" A.N.S.I. 900 • OVAL RING R49
28	GUARD, RISER, FOR 8" PIPE (COMPLETE)
29	HANGER, C-EVLS, FOR 8" PIPE (COMPLETE)
30	INSULATING, SET, 4" A.N.S.I. 600 • (COMPLETE)
31	INSULATING, SET, 16" A.N.S.I. 600 • (COMPLETE)
32	LUG, THOMAS AND BETTS NO. 32009
33	NIPPLE, PIPE, 1" X 3" LG. XH (T.B.E.)
34	NIPPLE, PIPE, 1" X 6" LG. XH (T.B.E.)
35	NIPPLE, PIPE, 1" X 6" LG. XH (T.O.E.)
36	PIG, INDICATOR, FOR 8" O.D. X .406" W.T. GR. B PIPE, KIDD MODEL 2005
37	PIPE, 2.375" O.D. X .218" W.T. GR. B U.S. Steel
38	PIPE, 4.500" O.D. X .337" W.T. GR. B U.S. Steel
39	PIPE, 8.625" O.D. X .426" W.T. GR. B 42° 30' DEG. U.S. Steel
40	PIPE, 8.625" O.D. X .500" W.T. GR. B Youngstown
41	PIPE, 8.625" O.D. X .500" W.T. GR. B Youngstown
42	PIPE, 10.750" O.D. X .500" W.T. GR. X-42 U.S. Steel
43	PIPE, 8.625" O.D. X .500" W.T. GR. B FOR 10" O.D. 100"
44	FABRICATED COLD BEND (11.2' LG.) U.S. Steel
45	PLUG, HEX, 1/2" A.N.S.I. 3000 P.S.I. STAINLESS STEEL SCRD.
46	PLUG, PEECO, 1/2" A.N.S.I. 3000 P.S.I. F.S. SCREWED (NYE-COATED)
47	REDUCER, CONCENTRIC, WELD, 16" O.D. X .500" W.T. X 8.625" O.D. X .500" W.T. GR. Y-52 (1.2' LG.)
48	REDUCER, CONCENTRIC, WELD, 6.625" O.D. X .432" W.T. X 4.500" O.D. X .337" W.T. GR. B (0.5' LG.)
49	REDUCER, ECCENTRIC, WELD, 10.750" O.D. X .500" W.T. X 8.625" O.D. X .500" W.T. GR. B (0.6' LG.)
50	SADDLE, STD. WELD, 2" X 8"
51	SADDLE, STD. WELD, 2" X 10"
52	SUPPORT, SHIM BLOCK, FOR 8" PIPE (COMPLETE)
53	SUPPORT, SHIM BLOCK, FOR 10" PIPE (COMPLETE)
54	TIE, WELD, 8.625" O.D. X .500" W.T. GR. B W/SCRAPER BARS (1.2' LG.)
55	THREDOLET, 2 1/2" - 2" X 1" 6000 P.S.I. F.S.
56	THREDOLET, 10" - 3" X 1" 6000 P.S.I. F.S. NPT
57	THREDOLET, 36" - 8" X 1/2" 6000 P.S.I. F.S. NPT
58	VALVE, BALL, 8" A.N.S.I. 600 • CAMERON (W/RTJ)
59	OPERATOR, RC 35 (5/8" 76850)
60	UNION, F.S. GJ INSUL, 1" A.N.S.I. 3000 • SCREWED
61	VALVE, BALL, 1" 3000 P.S.I. JAMESBURY NO. HP366T W/HANDLE
62	VALVE, BALL, 2" A.N.S.I. 600 • (W/RTJ)
63	VALVE, BALL, 4" A.N.S.I. 600 • W/MANUAL OPERATED GEARING AND HANDWHEEL (W/RTJ)
64	VALVE, BALL, 8" A.N.S.I. 600 • GROVE W/MANUAL OPERATED GEARING AND HANDWHEEL (W/RTJ)
65	VALVE, GLOBE, 1/2" FPT X 1/2" MPT 6000 • WHITEY TYPE 316SS
66	VALVE, TOM WHEATLEY SWING CHECK, 8" A.N.S.I. 600 • (RTJ/RTJ)
67	CLAMP, PIPE AND BRACE, FOR 8" PIPE (COMPLETE)
68	THRED-O-RING, 2" XH W/PIPE CAP AND BRACE PLUG T.D. WILLIAMSON TYPE

COATING "A" -- 3M Scotchkote 122

FOR CONTINUATION SEE:
DWG. TO-F2-823X-530-1A

THIS DWG. CURRENT THRU: 9-79

REFERENCE DRAWINGS		REVISIONS	
DRAWING NO.	TITLE	NO. DATE	REMARKS
TO-F2-823X-1600-1A	PLATFORM A-343 - PIPING DETAILS		



Tennessee Gas Pipeline Company

Division of Tenneco Inc.

Engineering Department

Houston, Texas

DRAWN BY D.L.	DATE 8-13-81
CHECKED BY AMJ	DATE 10-9-81
CORRECT BY JSM	DATE 11-5-81
DESIGNED BY	DATE
APPROVED BY HMM	DATE 11-6-81
ISSUE DATES	ORIGINAL 2-28-82
	LAST C-28-82

PIPING DETAILS


H.I.O.S.-HIGH ISLAND BLK. A-343 PLATFORM

HIGH ISLAND AREA, GULF OF MEXICO


APPROVED BY J.P. Hallenbeck
11.11.81
ASST. CHIEF ENGINEER

TENNESSEE GAS PIPELINE CO.


TO-F2-823X-1600-1A1




TENNECO OIL COMPANY - HIGH ISLAND
BLK. A-336A PLATFORM
PLAN
SCALE 3/32"=1'-0"



SECTION "B - B"
SCALE: 3/8"=1'-0"



DETAIL NO.
SCALE: 3/8" = 1'-0"



SECTION "A - A"
SCALE: 3/8" = 1'-0"

ITEM NO.	DESCRIPTION
1	BOLTS, STUD, 5/8" DIA. X 4 1/2" LG. ALLOY STEEL, W/2 HEX NUTS EACH.
2	BOLTS, STUD, 7/8" DIA. X 6" LG. ALLOY STEEL, W/2 HEX NUTS EACH.
3	BOLTS, STUD, 1 1/8" DIA. X 8" LG. ALLOY STEEL, W/2 HEX NUTS EACH.
4	BOLTS, STUD, 1 3/8" DIA. X 13" LG. ALLOY STEEL, W/2 HEX NUTS EACH.
5	BUSHING, 2" X 1 1/2" F.S. SCREWED, 6,000 P.S.I. WOG
6	CLAMP, PIPE AND BRACE, FOR 4" PIPE (COMPLETE)
7	CLAMP, RISER, FOR 8" PIPE
8	CLAMP, RISER, FOR 8" PIPE
9	CLAMP, RISER, FOR 8" PIPE
10	CLAMP, RISER, FOR 8" PIPE
11	CLAMP, RISER, FOR 3" PIPE
12	CLOSURE, HINGED, 10" A.N.S.I. 600 •
13	ELL. STREET, 1" A.N.S.I. 3000 • SCREWED
14	ELL. WELD, 2.375" O.D. X .218" W.T. GR.B 30" LR. (0.5" LG.)
15	ELL. WELD, 8.625" O.D. X .500" W.T. GR.B 30" LR. (2.0" LG.)
16	ELL. WELD, 8.625" O.D. X .500" W.T. GR.B 80"08" 301A. (3.0" LG.)
17	ELL. WELD, 8.625" O.D. X .500" W.T. GR.B 90" 301A. (4.0" LG.)
18	FLANGE, 2" A.N.S.I. 600 • RTJW BLND
19	FLANGE, 4" A.N.S.I. 600 • RTJWN
20	FLANGE, 8" A.N.S.I. 600 • RTJWN
21	FLANGE, 8" A.N.S.I. 900 • RTJWN
22	FLANGE, 8" A.N.S.I. 900 • RTJWN
23	GASKET, 2" A.N.S.I. 600 • OVAL RING R23
24	GASKET, 2" A.N.S.I. 600 • OVAL RING R49
25	GASKET, 8" A.N.S.I. 300 • OVAL RING R49
26	GUARD, RISER, FOR 8" PIPE (COMPLETE)
27	HANGER, CLEVIS, FOR 2" PIPE (COMPLETE)
28	HANGER, CLEVIS, FOR 8" PIPE (COMPLETE)
29	INSULATING, SET, 4" A.N.S.I. 600 • (COMPLETE)
30	INSULATING, SET, 8" A.N.S.I. 600 • (COMPLETE)
31	INSULATING, SET, 8" A.N.S.I. 600 • (COMPLETE)
32	INSULATING, SET, 8" A.N.S.I. 600 • (COMPLETE)
33	INSULATING, SET, 8" A.N.S.I. 600 • (COMPLETE)
34	INSULATING, SET, 8" A.N.S.I. 600 • (COMPLETE)
35	LUG, THOMAS AND BETT, NO.32009
36	NIPPLE, PIPE, 1" X 3" LG. XH (T.B.E.)
37	NIPPLE, PIPE, 1" X 5" LG. XH (T.B.E.)
38	NIPPLE, PIPE, 1" X 6" LG. XH (T.B.E.)
39	PIG, INDICATOR, FOR 8" O.D. X .500" W.T. GR.B PIPE, KIDCO MODEL 2005
40	PIPE, 2.375" O.D. X .218" W.T. GR.B U.S.Steel
41	PIPE, 4.500" O.D. X .337" W.T. GR.B U.S.Steel
42	PIPE, 8.625" O.D. X .406" W.T. GR. X-42 U.S.Steel
43	PIPE, 8.625" O.D. X .500" W.T. GR. B Youngstown
44	PIPE, 8.625" O.D. X .500" W.T. GR. B Youngstown (30" O" NEOPRENE COATED)
45	PIPE, 10.750" O.D. X .500" W.T. GR. X-42 U.S.Steel
46	PIPE, 8.625" O.D. X .500" W.T. GR. B FOR 10"0200"
47	FABRICATED COLD BIND 4" X 10"
48	PLUG, HEX, 1/2" A.N.S.I. 3000 P.S.I. STAINLESS STEEL SCRD.
49	PLUG, HEX, 1" A.N.S.I. 3000 P.S.I. STAINLESS STEEL SCRD.
50	PLUG, FLEECO, 1/2" A.N.S.I. 3000 P.S.I. F.S. SCREWED (NYE-COATED)
51	REDUCER, ECCENTRIC, WELD, 10.750" O.D. X .500" W.T. X 8.625" O.D. X .500" W.T. GR. B (0.6" LG.)
52	SADDLE, STD. WELD, 2" X 8"
53	SADDLE, STD. WELD, 2" X 10"
54	SADDLE, STD. WELD, 4" X 10"
55	SCOKLEET, COSASCO 10" - 2" NO. 120327
56	SUPPORT, SHIM BLOCK, FOR 8" PIPE (COMPLETE)
57	SUPPORT, SHIM BLOCK, FOR 8" PIPE (COMPLETE)
58	TEE, WELD, 8.625" O.D. X .500" W.T. GR. B W/CRAPPER BARS
59	THREDCOLT, 1/2" - 2" X 1" 6,000 P.S.I. F.S.
60	THREDCOLT, 10" - 3" X 1" 6,000 P.S.I. F.S. NPT
61	THREDCOLT, 10" - 3" X 1/2" 6,000 P.S.I. F.S. NPT
62	THREDCO-O-RING, 2" XH WELD NIPPLE W/MACHINED STEEL PIPE CAP AND BRASS PLUG
63	UNION, 3" S. GJ INSUL. 1" A.N.S.I. 3000 • SCREWED
64	VALVE, BALL, 1" 3000 P.S.I. JAMESBURY NO. HF36GT W/HANDLE
65	VALVE, BALL, 2" A.N.S.I. 600 • (W/R T J)
66	VALVE, BALL, 2" FPT 1500 W.K.M. FIG. NO. 310
67	VALVE, BALL, 4" A.N.S.I. 1200 • CAMERON W/MANUAL OPERATED GEARING AND HANDWHEEL (W/R T J)
68	VALVE, BALL, 8" A.N.S.I. 600 • GROVE W/MANUAL OPERATED GEARING HANDWHEEL (W/R T J)
69	VALVE, GLOBE, 1/2" FPT X 1/2" MPT 6000 • WHITEY TYPE 316SS
70	VALVE, TOM WHEATLEY SWING CHECK, 8" A.N.S.I. 600 • (RTJ T J)
71	FLANGE, 2" A.N.S.I. 600 • RTJWN
72	FLANGE, 2" A.N.S.I. 600 • RTJWN
73	FLANGE, 2" A.N.S.I. 600 • RTJWN
74	FLANGE, 2" A.N.S.I. 600 • RTJWN
75	FLANGE, 2" A.N.S.I. 600 • RTJWN
76	FLANGE, 2" A.N.S.I. 600 • RTJWN
77	FLANGE, 2" A.N.S.I. 600 • RTJWN
78	FLANGE, 2" A.N.S.I. 600 • RTJWN
79	FLANGE, 2" A.N.S.I. 600 • RTJWN
80	FLANGE, 2" A.N.S.I. 600 • RTJWN
81	FLANGE, 2" A.N.S.I. 600 • RTJWN
82	FLANGE, 2" A.N.S.I. 600 • RTJWN
83	FLANGE, 2" A.N.S.I. 600 • RTJWN
84	FLANGE, 2" A.N.S.I. 600 • RTJWN
85	FLANGE, 2" A.N.S.I. 600 • RTJWN
86	FLANGE, 2" A.N.S.I. 600 • RTJWN
87	FLANGE, 2" A.N.S.I. 600 • RTJWN
88	FLANGE, 2" A.N.S.I. 600 • RTJWN
89	FLANGE, 2" A.N.S.I. 600 • RTJWN
90	FLANGE, 2" A.N.S.I. 600 • RTJWN
91	FLANGE, 2" A.N.S.I. 600 • RTJWN
92	FLANGE, 2" A.N.S.I. 600 • RTJWN
93	FLANGE, 2" A.N.S.I. 600 • RTJWN
94	FLANGE, 2" A.N.S.I. 600 • RTJWN
95	FLANGE, 2" A.N.S.I. 600 • RTJWN
96	FLANGE, 2" A.N.S.I. 600 • RTJWN
97	FLANGE, 2" A.N.S.I. 600

COATING "A" -- 3M Scotchkote 212

THIS DWG. CURRENT THRU: 9-79

[illegible]

Tennessee Gas Pipeline Company

Division of Tenneco Inc.

Engineering Department'

Houston, Texas

DRAWN BY D.L.	DATE 4-4-81
CHECKED BY AMJ	DATE 10-9-81
CORRECT BY RSM	DATE 11-5-81
DESIGNED PY	DATE
APPROVED BY HMM	DATE 11-6-81
	SCALE SHOWN
ISSUE DATES	ORIGINAL 2-28-82

PIPING DETAILS

H.I.O.S.-HIGH ISLAND BLK. A-336A PLATFORM

HIGH ISLAND AREA, GULF OF MEXICO.

APPROVED BY *J.P. Kallman*
11-11-81 ASST. CHIEF ENGINEER

TENNESSEE GAS PIPELINE CO

TO-F2-823X-1600-1B1



United States Department of the Interior

MINERALS MANAGEMENT SERVICE
GULF OF MEXICO OCS REGION
1201 ELMWOOD PARK BOULEVARD
NEW ORLEANS, LOUISIANA 70123-2394

SN 5443
BEST AVAILABLE COPY

In Reply Refer To: LE-3-1
N. O. Misc. No. 014

November 30, 1989

ACTION

Tennessee Gas Pipeline Company

Right-of-Way

MERGER AND CHANGE OF NAME RECOGNIZED

On October 17, 1989, there was filed in this office for approval evidence of merger of Tenneco Merger Company, an unqualified corporation, with and into Tenneco Inc., a Delaware corporation (N. O. Misc. No. 014), and, as of the date of the merger, Tenneco Inc. changed its name to Tennessee Gas Pipeline Company. The effective date of the merger and simultaneous change of name is December 8, 1987. The name of the surviving corporation is Tennessee Gas Pipeline Company and the qualification number assigned thereto is New Orleans Miscellaneous File Number 014.

In connection with the merger and change of name, the following evidence was received:

1. Agreement and Plan of Merger of Tenneco Merger Company with and into Tenneco Inc. under the name of Tennessee Gas Pipeline Company, duly certified by the Secretary of State of the State of Delaware on December 8, 1987, with additional certification by James Gaughan, Assistant Secretary of Tennessee Gas Pipeline Company, on June 7, 1989;
2. Certificate reflecting that Tennessee Gas Pipeline Company is duly incorporated under the laws of the State of Delaware and is in good standing, executed by the Secretary of State of the State of Delaware, on November 3, 1988;
3. Certificate reflecting that Tennessee Gas Pipeline Company is incorporated under the laws of the State of Delaware and that it is authorized to hold pipeline rights of way and mineral leases on the Outer Continental Shelf, duly executed by Vincent F. Ewell, Jr., Assistant Secretary of Tennessee Gas Pipeline Company, on June 7, 1989;

4. Certificate listing the elected or appointed and now acting officers of Tennessee Gas Pipeline Company, duly executed by James Gaughan, Assistant Secretary of Tennessee Gas Pipeline Company, on June 7, 1989;
5. Copy of resolutions adopted at a meeting of the Board of Directors of Tennessee Gas Pipeline Company held on May 9, 1989, duly certified by James Gaughan, Assistant Secretary of Tennessee Gas Pipeline Company, on June 1, 1989;
6. Bond Rider to be attached to Outer Continental Shelf Right of Way Bond Number 61 S 33110-15-79 BCA changing the name of the principal to Tennessee Gas Pipeline Company, effective December 8, 1987;
7. Listing of the pipeline rights-of-way to be affected by the merger and change of name.


Since the transfer and vesting of property rights in the surviving corporation have been effected by State statutes by operation of law and not by individual conveyances, the merger and change of name are hereby approved insofar as they affect pipeline rights-of-way under 30 CFR 250. The change in ownership as to the pipeline rights-of-way listed below is recognized and the records so noted:

<u>OCS-G NO.</u>	<u>OCS-G NO.</u>	<u>OCS-G NO.</u>	<u>OCS-G NO.</u>	<u>OCS-G NO.</u>
0643	1345	1692	1854	2121-E
0643-A	1376	1702	1854-A	2123
0643-B	1382	1702-B	1854-B	2214
0643-C	1382-A	1702-C	1854-C	2214-A
0643-D	1383	1702-D	1854-E	2975
0649	1434	1702-E	1854-F	2975-A
0875	1434-A	1702-F	1854-G	3221
0877	1434-G	1702-H	1854-H	3221-A
0885	1434-H	1702-I	1854-I	3348
0886	1434-J	1702-K	1907-W	3349
0887	1434-K	1702-L	1950-J	3350
0887-A	1461	1702-M	1950-L	3355
0889	1464	1702-O	1992	3357
0891	1464-A	1702-P	2121	3358
0891-A	1683	1702-Q	2121-A	3360
0892	1684	1702-R	2121-B	3437
0895	1687-S	1702-S	2121-C	3449
1320	1687-T	1702-T	2121-D	3451

N. O. Misc. No. 014

Page 3

<u>OCS-G NO.</u>	<u>OCS-G NO.</u>	<u>OCS-G NO.</u>	<u>OCS-G NO.</u>	<u>OCS-G NO.</u>
3455	4028	4290	4855	7109
3613	4030	4291	4977	7535
3614	4040	4306	5135	7536
3626	4043	4308	5136	7552
3633	4061	4309	5137	7554
3638	4150	4340	5141	7575
3644	4154	4341	5152	7576
3648	4158	4373	5157	7587
3652	4160	4374	5232	8046
3828	4161	4526	5253	8047
3837	4169	4603	5259	8050
3845	4171	4605	5933	8056
3848	4173	4608	5937	8057
3851	4276	4609	6381	8527
3852	4282	4613	6546	8617
3855	4283	4641	7096	10396
3861	4284	4644	7104	11165
3862	4287	4686	7107	11174


J. Rogers Pearcy
Regional Director

cc: Associates
Case Files
Qualification File (N. O. Misc. No. 014)

5N5443

BEST AVAILABLE COPY

MAY 23 1984

In Reply Refer To: RP-2-2
OCS-G 4040

ACTION

Tenneco Inc. : Pipe Line Right-of-Way
: :
: Date of Permit: 8/14/79
: :
: Decision Requesting Proof of
: Construction Dated:
: :
: Proof of Construction
: Received: 5/4/84

Proof of Construction Accepted

The above-captioned grantee has submitted the evidence required by the law and Regulations 30 CFR 256.95(a). The proof of construction is hereby accepted and approved. Deviation from the original plat has been noted and new plat made a part of the record.

Because grantee has deviated from the approved right-of-way by ± 25 feet in Block A-343, High Island Area, East Addition, South Extension, Tenneco Inc. must notify Exxon Corporation, operator of Lease OCS-G 2741, to that effect. A return-receipt-card or letter from Exxon Corporation evidencing proof of notice must be submitted to this office within 60 days of receipt hereof. The total length of the "as-built" 8 5/8-inch pipeline right-of-way is 1.66 miles.

(Orig. Sgd.) John L. Rankin

John L. Rankin
Regional Manager

CERTIFIED MAIL NO. P21 4379111

bcc: P/L OCS-G 4040 (LE)
P/L OCS-G 4040 (w/attachments) (RP-2-2)
RM Reading File

ABritton:lv:5/21/84:Disk 6

*already on map
as "no-build"
K7
7/3/84*

Tennessee Gas Pipeline
Division of Tenneco Inc.

P.O. Drawer 53388
Lafayette, Louisiana 70505
(318) 233-7802



April 2, 1984

Minerals Management Service
Rules and Production (RP-2-2)
Mr. D. W. Solanas, Regional Supervisor
P. O. Box 7944
Metairie, Louisiana 70010

Re: Proof of Construction
OCS-G 4040 Pipeline Right of Way
High Island Area (Gulf of Mexico)
High Island Blk. 336-B Line


Dear Mr. Solanas:

On August 7, 1979, application for pipeline right of way was approved and permit issued for the construction of a ten inch (10") natural gas pipeline in the High Island area, Gulf of Mexico, Louisiana.


In accordance with regulations 43 CFR 3340.3, we attach herewith, in triplicate, the as-constructed drawing No. TO-F2-823X-1600-1, showing the deviation from the right of way as originally planned and submitted, along with duplicate copies of hydrostatic test data.

If there is any additional information needed pertaining to this matter, please advise.

Yours very truly,


R. S. Perot
Assistant Division
Right of Way Supervisor

RSP/jsb
Enclosure



cc: R. L. Sanderson
H. M. McLeod
R. E. Lyons
J. C. Broome, III

R. G. Robertson
J. D. DeBlieux
F. J. Millette, Jr.
File

AS-CONSTRUCTED

NOTE: SEE PROCEDURE TGT 6-129
FOR INSTRUCTIONS

PIPE TEST REPORT OCS-G4-040 823X-1600

SHEET 1 OF 1 #293


C.O. NO. 46673	DISTRICT 823	LINE NO. 823X-1600	SPREAD CHICKASAW	SECTION I	DATE 9-9-79
DRAWING NO. TE-F2-823X-1600-1	LOCATION 823X- FROM MLV 1601 TO MLV 1602	SECTION TESTED	FROM STA. 0+91	TO STA. 94+60.2	FOOTAGE 8801.9' Live 567.3' Riser Tab
NOMINAL PIPE 100% S.M.Y.S. PRESSURE 3297 PSIG	SIZE O.D. 8.625 IN.	W.T. .406 IN.	GRADE B	MFR. U.S.S.	
HYDROSTATIC TEST CONTRACTOR SANTA FE	M.A.O.P.	PIPELINE CONTRACTOR SANTA FE	PROJECT MANAGER GEORGE GERONON		
COMPANY PERSONNEL INVOLVED 1 TENNESSEE GAS INSPECTOR - L.R. SLOWIK George Benoit					
TEST MEDIUM (WATER, GAS, AIR, OTHER) SEAWATER					

	END OF TEST SECTION	PRESSURE POINT	HIGH ELEVATION	LOW ELEVATION	END OF TEST SECTION
MAP PLUS	94+60.2	0+91.2	94+60.2	0+80.0	0+91.0
ELEVATION (FEET)	+50	+11	+50	0	+11
TEST PRESSURE (PSI)	2165	2169.9	2165	2187	2169.9
% S.M.Y.S.	65.6%	65.8%	65.6%	66.3%	65.8%

TEST SKETCH (ATTACH ADDITIONAL SKETCH SHEET IF NECESSARY)

FLOW

TEST SECTION NO. 0+00



USEFUL CONVERSION FACTORS:	1 FOOT OF WATER = .433 PSI 1 PSI = 2.31 FEET OF WATER	WATER SOURCE SEA WATER	MILE POST	WATER SOURCE TEMPERATURE
DEVIATION DATA (OBSERVED AT PRESSURE PT)	INITIAL DEVIATION:	PRESSURE PSIG	% S.M.Y.S.	
	FINAL DEVIATION:	PRESSURE PSIG	% S.M.Y.S.	DEVIATION PSI
FAILURE DATA (OBSERVED AT FAILURE PT)	DATE	TIME	A.M. P.M.	MAP STATION
				ELEVATION
	DESCRIPTION (ATTACH SKETCH OR PHOTO)		REPAIRS MADE (USE BACK IF NEEDED)	
<input type="checkbox"/> ALL TIE-IN WELDS WERE NONDESTRUCTIVELY TESTED METHOD:				BY

ELEVATION DATA DERIVED FROM PROFILE SHEET TE-

OR U.S.G.S. QUAD SHEET:


TEST REJECTED	TEST ACCEPTED	DATE
NOTE: SEE ABOVE FAILURE DATA	TEST INSPECTOR SIGNATURE: J.B. Slowik	9-9-79
	DISTRICT SIGNATURE: J.B. Centry	11/20/79
SIGNATURE: BEST AVAILABLE COPY	DIVISION SIGNATURE: R.H. Lohman	11-26-79
DATE:	AGENCY SIGNATURE:	

REMARKS: (TEST, WEATHER, BLEED OFF, OFF TEST,
NO. OF STROKES FOR REPRESSURE, ETC.)

COMMENTS:

BEST AVAILABLE COPY

BEST AVAILABLE COPY



NOTE: SEE PROCEDURE TGT 6-129
FOR INSTRUCTIONS

PIPE TEST REPORT **OCS-G4040** **823X-1600**

C.O. NO. 46673	DISTRICT 823	LINE NO. 823X-1600	SPREAD YARD Santa Fe	SECTION III	DATE 8-31-79
DRAWING NO. TE-F2-823X-1600-1B		LOCATION FROM MLV YARD TO MLV	SECTION TESTED FROM STA. YARD TO STA.		FOOTAGE 35 FT.
NOMINAL PIPE: 16 IN.	SIZE O.D. 16 IN.	W.T. .500 IN.	GRADE < 52		
100% S.M.Y.S. PRESSURE 3250 PSIG		M.A.O.P.		MFR. U.S.S.	
HYDROSTATIC TEST CONTRACTOR Santa Fe ENGR. & Const.		PIPELINE CONTRACTOR Santa Fe ENGR. & Const.			
COMPANY PERSONNEL INVOLVED A.E. White		PROJECT MANAGER George BERNIN			
TEST MEDIUM (WATER, GAS, AIR, OTHER) FRESH water					

	END OF TEST SECTION	PRESSURE POINT	HIGH ELEVATION	LOW ELEVATION	END OF TEST SECTION
MAP PLUS		YARD	Tested	Pipe	
ELEVATION (FEET)					
TEST PRESSURE (PSI)	2160	2160	2160	2160	2160
% S.M.Y.S.	66.4%	66.4%	66.4%	66.4%	66.4%

TEST SKETCH (ATTACH ADDITIONAL SKETCH SHEET IF NECESSARY) FLOW → TEST SECTION NO. _____

M.P.
+
20 Ft
8.625" AD x .500 WT
MISH WISCH Tie-in

RECEIVED
APR 04 1984
Minerals Management Bureau
Rules and Reg.
3'-6 1/2"
6'-3"
UNITED GAS Tie-in

AS-CONSTRUCTED

USEFUL CONVERSION FACTORS:	<ul style="list-style-type: none"> 1 FOOT OF WATER = .433 PSI 1 PSI = 2.31 FEET OF WATER 	WATER SOURCE	MILE POST	WATER SOURCE TEMPERATURE			
DEVIATION DATA (OBSERVED AT PRESSURE PT)	INITIAL DEVIATION:	PRESSURE PSIG	% S.M.Y.S.	DEVIATION PSI			
	FINAL DEVIATION:	PRESSURE PSIG	% S.M.Y.S.				
FAILURE DATA (OBSERVED AT FAILURE PT)	DATE	TIME	A.M. P.M.	MAP STATION	ELEVATION	FAILURE PRESSURE PSIG	% S.M.Y.S.
	DESCRIPTION (ATTACH SKETCH OR PHOTO)				REPAIRS MADE (USE BACK IF NEEDED)		

☐ ALL TIE-IN WELDS WERE NONDESTRUCTIVELY TESTED

METHOD: _____ BY: _____

ELEVATION DATA DERIVED FROM PROFILE SHEET TE- _____ OR U.S.G.S. QUAD SHEET: _____


TEST REJECTED	TEST ACCEPTED	DATE
NOTE: SEE ABOVE FAILURE DATA BEST AVAILABLE COPY SIGNATURE: _____ DATE: _____	TEST INSPECTOR SIGNATURE: A.E. White	8-31-79
	DISTRICT SIGNATURE: S.B. Custer	11/20/79
	DIVISION SIGNATURE: R.H. Rokutian	11-26-79
	AGENCY SIGNATURE: _____	

TABLE OF TEST PRESSURES

DATE	TIME	DEAD WEIGHT	TEMPERATURE		REMARKS: (ON TEST, WEATHER, BLEED OFF, OFF TEST, NO. OF STROKES FOR REPRESSURE, ETC.)
			TEST WATER	AMBIENT	
8/31/79	1830	2174	66°	88°	BEGIN TEST
	1845	2174	66°	88°	
	1900	2174	66°	88°	
	1915	2172	66°	87°	
	1930	2170	66°	85°	
	1945	2168	66°	85°	
	2000	2164	66°	84°	REPRESSURE 2161-2175
	2015	2175	66°	84°	
	2030	2173	66°	84°	
	2045	2173	66°	84°	
	2100	2167	66°	82°	
	2115	2164	66°	82°	REPRESSURE 2163-2179
	2130	2170	66°	82°	
	2145	2166	66°	82°	2162-2173
	2200	2175	66°	82°	
	2215	2166	66°	81°	2170-2175
	2230	2163	66°	81°	
	2245	2161	66°	80°	2160-2165
	2300	2171	66°	80°	2160-2175
	2315	2163	65°	80°	
	2330	2175	65°	80°	2160-2175
	2345	2169	65°	80°	
9-1-79	2400	2161	65°	80°	
	0015	2170	65°	80°	2160-2175
	0030	2166	65°	80°	
	0045	2160	65°	80°	
	0100	2175	65°	80°	2160-2175
	0115	2172	65°	80°	
	0130	2166	65°	80°	
	0145	2160	65°	80°	2160-2175
	0200	2173	65°	80°	
	0215	2168	65°	80°	
	0230	2164	65°	80°	END OF TEST

COMMENTS:

BEST AVAILABLE COPY



CALIBRATED
CHARTS


H.I. B.K. 336 A.L.N.
8-31-79

LD 46673

PRESS.
BR-B0-5000-12

SIGNED *[Signature]*

BEST AVAILABLE COPY



CALIBRATED
CHARTS
DATAVIA
N.Y.

H.I. BLC 336A LU
8-31-79
CO 46673


TEMP.

MW-MP 300

SIGNED Bull White

BEST AVAILABLE COPY

BEST AVAILABLE COPY



GENERAL NOTE

1) CONSTRUCTION OF THE BUILDING SHALL BE IN ACCORDANCE WITH THE LATEST EDITIONS OF THE BUILDING CODES AND STANDARDS. ALL MATERIALS AND WORKMANSHIP SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE AUTHORITY.

2) THE OWNER SHALL BE RESPONSIBLE FOR THE PROVISION OF ALL NECESSARY SERVICES AND UTILITIES TO THE BUILDING.

3) THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISION OF ALL NECESSARY PERMITS AND APPROVALS FOR THE CONSTRUCTION OF THE BUILDING.

4) THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISION OF ALL NECESSARY SAFETY MEASURES DURING THE CONSTRUCTION OF THE BUILDING.

5) THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISION OF ALL NECESSARY PROTECTION MEASURES TO THE EXISTING BUILDING AND SURROUNDING AREA.

6) THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISION OF ALL NECESSARY ACCESS MEASURES TO THE EXISTING BUILDING AND SURROUNDING AREA.

7) THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISION OF ALL NECESSARY PROTECTION MEASURES TO THE EXISTING BUILDING AND SURROUNDING AREA.

8) THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISION OF ALL NECESSARY PROTECTION MEASURES TO THE EXISTING BUILDING AND SURROUNDING AREA.

9) THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISION OF ALL NECESSARY PROTECTION MEASURES TO THE EXISTING BUILDING AND SURROUNDING AREA.

10) THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISION OF ALL NECESSARY PROTECTION MEASURES TO THE EXISTING BUILDING AND SURROUNDING AREA.

DTE: SEE PROCEDURE TGT 6.129
FOR INSTRUCTIONS

PIPE TEST REPORT

823X-1600 TEST #2 of 3


C.O. NO. 46673	DISTRICT 823	LINE NO. 823X-1600	SPREAD YARD	SECTION	DATE AUG. 22 1979
DRAWING NO. TE-F2 823X-1602-1		LOCATION FROM MLV TO MLV		SECTION TESTED FROM STA. TO STA.	FOOTAGE
NOMINAL PIPE:	SIZE O.D. 12.750 IN.	W.T. .500 IN.	GRADE X-42	MFR.	
100% S.M.Y.S. PRESSURE 3294 PSIG		M.A.O.P. PSIG		PIPELINE CONTRACTOR SANTA FE	
HYDROSTATIC TEST CONTRACTOR SANTA FE				PROJECT MANAGER GEORGE GERON	
COMPANY PERSONNEL INVOLVED KEITH KIRKLAND					
TEST MEDIUM (WATER, GAS, AIR, OTHER) WATER					

	END OF TEST SECTION	PRESSURE POINT	HIGH ELEVATION	LOW ELEVATION	END OF TEST SECTION
MAP PLUS	0	0	0	0	0
ELEVATION (FEET)	0	0	0	0	0
TEST PRESSURE (PSI)	2161	2161	2161	2161	2161
% S.M.Y.S.	66	66	66	66	66

TEST SKETCH (ATTACH ADDITIONAL SKETCH SHEET IF NECESSARY)

FLOW

TEST SECTION NO.



FOR DETAILS SEE DRAWING 823X-1602-1

RECEIVED

APR 04 1984

BEST AVAILABLE COPY

AS-CONSTRUCTED

Macrols Management
Rules and Regulations

USEFUL CONVERSION FACTORS:	• 1 FOOT OF WATER = .433 PSI • 1 PSI = 2.31 FEET OF WATER	WATER SOURCE CITY TAP	MILE POST N-A.	WATER SOURCE TEMPERATURE 70°
DEVIATION DATA (OBSERVED AT PRESSURE PT)	INITIAL DEVIATION:	PRESSURE PSIG	% S.M.Y.S.	
	FINAL DEVIATION:	PRESSURE PSIG	% S.M.Y.S.	DEVIATION PSI
FAILURE DATA (OBSERVED AT FAILURE PT)	DATE	TIME	A.M. P.M.	MAP STATION
	ELEVATION		FAILURE PRESSURE PSIG % S.M.Y.S.	
DESCRIPTION (ATTACH SKETCH OR PHOTO)			REPAIRS MADE (USE BACK IF NEEDED)	
<input type="checkbox"/> ALL TIE-IN WELDS WERE NONDESTRUCTIVELY TESTED METHOD:				BY

ELEVATION DATA DERIVED FROM PROFILE SHEET TE-

OR U.S.G.S. QUAD SHEET:

TEST REJECTED

TEST ACCEPTED

DATE

NOTE: SEE ABOVE FAILURE DATA

SIGNATURE:

BEST AVAILABLE COPY

DATE:

TEST INSPECTOR

SIGNATURE:

DISTRICT

SIGNATURE:

DIVISION

SIGNATURE:

AGENCY

SIGNATURE:

8/22/79
11/20/79
11-26-79

OF TEST PRESSURES

DATE	TIME	DEAD WEIGHT	TEMPERATURE		REMARKS: (ON TEST, WEATHER, BLEED OFF, OFF TEST, NO. OF STROKES FOR REPRESSURE, ETC.)
			TEST WATER	AMBIENT	
	4:50				Test slide started at 4:50 P.M.
8/22/79	4:50 P.M.	2174	70°	86°	End at 8:50 P.M.
	5:00	2167	70°	85°	
	5:15	2169	70°	83°	
	5:30	2164	70°	82°	
	5:45	2169	67°	82°	
	6:00	2163	65°	82°	
	6:15	2168	65°	82°	
	6:30	2166	68°	82°	
	6:45	2164	66°	80°	
	7:00	2166	64°	80°	
	7:15	2167	62°	80°	
	7:30	2175	60°	80°	
	7:45	2164	60°	80°	
	8:00	2173	60°	80°	
	8:15	2163	60°	79°	
	8:30	2168	60°	79°	
	8:45	2161	60°	79°	
	9:00 P.M.	2161	60°	79°	End of test

COMMENTS:

Deadweight name. Chandler Engineering #11074 1/3/79
 Pressure Recorder Barton #242A-9012 Calibrated 6/8/79
 Temp Recorder. Bal Barton #242A-4163 Calibrated 5/30/79

Andy Cotton

BEST AVAILABLE COPY

PLAN

3/8" = 1' 0"

END T.S.P.
NAT'L

* 6" BACK PRESS. REGULATOR
TO BE FURNISHED BY
TENNECO OIL CO.

6" 81-600PSI TURBINE METER
MOD. T-60 DIRECT READING


LEFT
ALE

TUBE #2


N. 21

KID

AR
SC



BEST AVAILABLE COPY



BEST AVAILABLE COPY

10 A.M.

11 A.M.

12
NOON

1 P.M.

BEST AVAILABLE COPY

2 P.M.

3 P.M.

4 P.M.

5 P.M.

6 P.M.

7 P.M.

8 P.M.

9 P.M.

10 P.M.

11 P.M.

**CALIBRATED
HARTS**
BATAVIA
N.Y.

METER NUMBER

TIME PUT ON

DATE PUT ON

19

TUBE & ORIF. SIZE

TIME TAKEN OFF

DATE TAKEN OFF


19

BR-2259

B 6-300-1371

SIGNED

[Signature]




$$\frac{3}{8}'' = 1' - 0''$$

MAT'L

* 6" BACK PRESS. REGULATOR
TO BE FURNISHED BY
TENNECO OIL CO.

(61) 8"-600PSI TURBINE METER
MOD. T-60 DIRECT READING




$$\frac{3}{8}'' = 1'-0''$$

MAT'L

BEST AVAILABLE COPY

* 6" BACK PRESS. REGULATOR
TO BE FURNISHED BY
TENNECO OIL CO.

(61) 8"-600PSI TURBINE METER
MOD. T-60 DIRECT READING




NOTE: SEE PROCEDURE TGT 6-129 FOR INSTRUCTIONS

PIPE TEST REPORT OCS-G4040 823X-1600

C.O. NO. 46673	DISTRICT 823	LINE NO. 823X-1600	SPREAD Santa Fe	SECTION II	DATE 7-28-79
DRAWING NO. TE-F2-823X-1600-1D	LOCATION FROM MLV -1B1 Yard Tested TO MLV	SECTION TESTED FROM STA. YARD	TO STA.		FOOTAGE
TE-F2-823X-1602-1	SIZE O.D. 8.625 IN.	W.T. .500 IN.	GRADE B	MFR. Youngstown Steel	
100% S.M.Y.S. PRESSURE 4057 PSIG		M.A.O.P.		PIPELINE CONTRACTOR SANTA Fe Const. Co.	
HYDROSTATIC TEST CONTRACTOR Santa Fe Contractors			PROJECT MANAGER George Gernow.		
COMPANY PERSONNEL INVOLVED Andy Cotton, Gerald McRae, Gene Haynes					RECEIVED APR 04 1984
TEST MEDIUM (WATER, GAS, AIR, OTHER) Tested with city water					

	END OF TEST SECTION	PRESSURE POINT	HIGH ELEVATION	LOW ELEVATION	TEST SECTION
MAP PLUS	Testing done @ Santa Fe Fab. yd. Nouma, LA.				
ELEVATION (FEET)	0	0	0	0	0
TEST PRESSURE (PSI)	2160	2160	2160	2160	2160
% S.M.Y.S.	53 %	53 %	53 %	53 %	53 %



USEFUL CONVERSION FACTORS: • 1 FOOT OF WATER = .433 PSI • 1 PSI = 2.31 FEET OF WATER	WATER SOURCE city water	MILE POST	WATER SOURCE TEMPERATURE 105° To 110°
DEVIATION DATA (OBSERVED AT PRESSURE PT)	INITIAL DEVIATION: 2172 PSIG	% S.M.Y.S.	
	FINAL DEVIATION: 2172 PSIG	% S.M.Y.S.	2160 To 2175 PSI
FAILURE DATA (OBSERVED AT FAILURE PT)	DATE	TIME	A.M. P.M.
	MAP STATION	ELEVATION	FAILURE PRESSURE PSIG
	DESCRIPTION (ATTACH SKETCH OR PHOTO)		
	REPAIRS MADE (USE BACK IF NEEDED)		

☒ ALL TIE-IN WELDS WERE NONDESTRUCTIVELY TESTED BY _____


METHOD _____


ELEVATION DATA DERIVED FROM PROFILE SHEET TE- _____ OR U.S.G.S. QUAD SHEET: _____

TEST REJECTED BEST AVAILABLE COPY	TEST ACCEPTED	DATE
NOTE: SEE ABOVE FAILURE DATA	TEST INSPECTOR SIGNATURE: Gerald E. McRae	7-28-79
SIGNATURE: _____	DISTRICT SIGNATURE: S.B. Cutting	11/20/79
	DIVISION SIGNATURE: L.H. Robertson	11-26-79
DATE: _____	AGENCY SIGNATURE: _____	

Tested Platform piping - High Island BLK A-336 A & Platform piping A-343 Both Assemblies Together.

BEST AVAILABLE COPY







BEST AVAILABLE COPY

TAX
DISTRICT
DATA

OWNERSHIP & LINE LIST NO.
H.I.O.S.-HIGH ISLAND BLK.A-336A

UNITED STATES OF AMERICA
GULF OF MEXICO



PT.	BEARING & DISTANCE	LAMBERT COORDINATES
1	N 72°52'45"W - 622.95'	X=3,694,328.97' Y=13,646.72'
2	N 72°52'45"W - 622.95'	X=3,693,935.47' Y=13,830.08'
3	N 52°04'32"W - 374.93'	X=3,693,637.91' Y=13,260.52'
4	N 64°01'25"W - 1,055.02'	X=3,692,681.83' Y=12,507.92'
5	N 62°19'04"W - 494.61'	X=3,692,216.96' Y=12,737.71'
6	N 62°59'40"W - 449.37'	X=3,691,836.14' Y=12,920.52'
7	N 61°10'39"W - 612.39'	X=3,691,272.60' Y=13,230.41'
8	N 72°41'44"W - 428.65'	X=3,690,863.60' Y=13,357.96'
9	N 70°28'56"W - 495.47'	X=3,690,396.76' Y=13,525.19'
10	N 53°01'27"W - 50.35'	X=3,689,979.81' Y=13,837.06'
11	N 72°24'58"W - 495.14'	X=3,689,496.87' Y=13,944.93'
12	N 66°21'13"W - 557.29'	X=3,688,966.31' Y=14,168.46'
13	N 63°40'10"W - 477.53'	X=3,688,558.26' Y=14,380.27'
14	N 61°47'21"W - 1,025.26'	X=3,687,651.15' Y=14,866.81'
15	N 72°44'11"W - 1,294.57'	X=3,686,415.25' Y=15,251.00'

PROFILE
SCALE: HORIZ: 1"=400 FT.
VERT: 1"= 20 FT.

LINE WAS LAID IN ACCORDANCE
WITH REQUIREMENTS OF B.L.M.
PERMIT AS ISSUED

BEST AVAILABLE COPY

NOTE: CO-ORDINATES ON POINTS 1-15 WERE ESTABLISHED BY ODOM OFFSHORE SURVEY & ASSOC. SURVEY BEARINGS AND DISTANCES WERE CALCULATED USING THE LAMBERT GRID (LOUISIANA SOUTH ZONE) SYSTEM. THE ROUTE AS SHOWN MAY NOT NECESSARILY BE THE EXACT LOCATION OF THE PIPELINE.

LOCATION OF RIGHT-OF-WAY
HAS BEEN ACCURATELY
DELINEATED UPON THIS MAP
Harry M. McCleod
HARRY M. McCLEOD
TEXAS REGISTERED PROFESSIONAL
ENGINEER N°14093



MATERIAL SUMMARY	
ITEM NO.	DESCRIPTION
1	ANODES, CYLINDRICAL B"
2	PIPE, 8.625"O.D. X .406"W.T. GR. X-42 U.S. Steel
3	PIPE, 8.625"O.D. X .500"W.T. GR. B Youngstown
COATING "A" --- 3M Scotchote 212 SN 5443 OCS-G 4040	
RECEIVED APR 04 1984 Tennessee Gas Pipeline Co. Valve Management Services Rules and Production	

C.O. NUMBER & DESCRIPTION		REFERENCE DRAWINGS		Tennessee Gas Pipeline Company		H.I.O.S.- HIGH ISLAND BLK.A-336A LN.		APPROVED BY	
PRELIM		DRAWING NO.	TITLE	Division of Tenneco Inc.	Engineering Department	LINE NO. 823X-1600		ASST. CHIEF ENGINEER	
CONST.	13862	TO-F2-823X-1600-1A & 1A1	PIPING DETAILS PLATFORM A-343A						
FINAL	13862	TO-F2-823X-1600-1B & 1B1	PIPING DETAILS PLATFORM A-336A						
LOG NOTES	13867								
				Houston, Texas		HIGH ISLAND AREA, GULF OF MEXICO		TENNESSEE GAS PIPELINE CO.	
						TO-F2-823X-1600-1			

3340 (210)


March 24, 1980

Tenneco, Inc.
Attention: F. J. Millette
P. O. Box 53388
Lafayette, Louisiana 70505

Gentlemen:

Please furnish proof of construction in accordance with 43 CFR 3340.3 on the following pipeline rights-of-way:

<u>OCS-G Number</u>	<u>Decision Issued</u>	<u>OCS-G Number</u>	<u>Decision Issued</u>
3360	9-15-76	4061	9-20-79
3640	12-16-77	4150	10-09-79
3645	3-22-78	4154	10-11-79
3837	8-25-78	4158	10-11-79
3867	11-02-78	4160	10-22-79
3873	11-02-78	4161	10-22-79
4028	6-12-79	4169	11-05-79
4029	8-09-79	4171	12-13-79
4030	7-23-79	4172	12-13-79
<u>4040</u>	8-14-79	4173	12-13-79


H. P. Sieverding
Acting Manager

210:DW11d:prb:3/24/80

NOTIFICATION OF CONSTRUCTION:

Company representative furnishing the following information R.S. PerotTelephone Number (318) 233-7802 Date 8-27-79

1. OCS Number G 4040
2. Name of Company Tenneco, INC.
3. Name of Contractor Santa Fe Engineering
4. Name of lay barge ??
5. Size of Pipeline 10.75 -INCH GAS 1.68 miles long
6. From where to where Tenneco INC's "B" Platform in Block A-336 to 30"
HIDS. P/L IN BLOCK A-343, all located in High Island Area.
7. Where construction begins and ends (i.e., which platform) A-343 to
A-336
8. Method of laying Conventional ?
9. How long barge will be on job 30 days Lay + Connection
10. Where heliports are available On Barge
11. Does the pipeline cross safety fairway(s)? (Go to map for information) NO.

Where _____

Initial and terminal points: Initial: X = _____ Y = _____

Terminal: X = _____ Y = _____

12. When the barge will begin (date) August 27, 1979

Notify: Frank Torres, U. S. Geological Survey, 837-4720, Ext. 237 (Give him items 1 10 & 12)). Date Contacted N/A

Notify only if construction crosses or in close proximity of fairways Chief O'Neil, Petty Officer Lutali, or Chief Flannegan, U. S. Coast Guard, telephone #6236 (upstairs). Give items 1 - 9 & 11 - 12. Date Contacted N/A

Items 1, 2, 5, 6, and 11 can be determined from the file if the company representative doesn't know them. Item 11 should be determined on a map in this office (see Bill Overstreet).

BLM Employee  8-28-79

Tennessee Gas Pipeline
Division of Tenneco Inc

P.O. Drawer 53388
Lafayette, Louisiana 70501
(318) 233-7802



AJO
8-28-79

August 24, 1979

The Bureau of Land Management
U. S. Dept. of The Interior
Hale Boggs Federal Building
500 Camp Street, Suite 841
New Orleans, Louisiana 70113

Attn: Chief, Division of Operations

Your Re: OCS-G 4040

Our Re: H. I. Blk. A-336B Line

Dear Sir:

Please be advised that Tennessee Gas Pipeline Company's contractor, Santa Fe Engineering, plans to start construction on the above captioned line on or before August 27, 1979. The lay barge does have a heliport.

Yours very truly,

R. S. Perot
Right of Way Agent

RSP/jsb

cc: R. L. Sanderson
L. J. Broussard
H. E. Fisher
R. G. Robertson
J. D. DeBlieux
F. J. Millette, Jr.
File

NEW ORLEANS

FILE CODE	INITIAL
ROUTE	
MGR.	
ASST. MGR.	
AUG 27 1979	
P. LEGAL	
PAO	
EAD	
OPS	
STUDIES	
MGMT. SER.	

RECEIVED
AUG 27 11 35 AM '79
BUR OF LAND MGMT.
OUTER CONTINENTAL
SHELLE OFFICE
NEW ORLEANS, LA

SN 5443
BEST AVAILABLE COPY

OCS-G 4040

High Island Area

East Addition,
South Extension
Blocks A-336, A-343

August 7, 1979

Tenneco Inc.

AUG 20 1979

Right-of-Way

ACTION - APPLICATION APPROVED

Your application for a 10" natural gas pipeline (H.I.O.S. A-336-B Line) dated May 11, 1979, with its attachments is approved with the following additions and corrections:

1. The guidelines for preparation of a pipeline application that are applicable and agreed to by the applicant are dated February 13, 1978.
2. The ANSI 600 valves, flanges and fittings should not be subjected to a body test greater than 2,175 psig.
3. Hydrostatic test data will be furnished this office within ninety (90) days following the test.

The permittee agrees that if any site, structure, or object of historical or archaeological significance should be discovered during the conduct of any operations within the permitted right-of-way, he shall report immediately such findings to the Manager, New Orleans OCS Office, and make every reasonable effort to preserve and protect the cultural resource from damage until the Manager, New Orleans OCS Office, has given directions as to its preservation.

Permittee agrees to comply with all regulations and conditions as may be prescribed by the Secretary of the Interior, or the Secretary of Transportation including, pursuant to section 21(b) of the OCS Lands Act, as amended, provisions to assure maximum environmental protection by utilization of the best available and safest technologies, including the safest practices for pipeline burial. This agreement includes but is not limited to complying with the following stipulations:

1. Permittee shall transport or purchase without discrimination oil or natural gas produced from submerged lands or outer Continental Shelf lands in the vicinity of its pipeline in such proportionate amounts as the Federal Energy Regulatory Commission, in consultation with the Secretary of Energy, may, after a full hearing with due notice

NOTED-MC INTOSH

BEST AVAILABLE COPY

Tenneco Inc.

-2-

OCS-G 4040

thereof to the interested parties, determine to be reasonable, taking into account, among other things, conservation and the prevention of waste.

2. Permittee shall operate its pipeline in accordance with the competitive principles set out in section 5(f)(1) of the Outer Continental Shelf Lands Act, as amended, except insofar as the Federal Energy Regulatory Commission may, by order or regulation, exempt such pipeline from any or all of the requirements of section 5(f)(1) pursuant to section 5(f)(2) (which permits such exemption of any pipeline or class of pipelines which feeds into a facility where oil and gas are first collected or a facility where oil and gas are first separated, dehydrated, or otherwise processed).
3. Unless so exempted by Federal Energy Regulatory Commission order or regulation, permittee shall operate its pipeline so as to provide open and nondiscriminatory access to both owner and nonowner shippers, and permittee shall comply with any specific conditions which the Secretary of Energy and the Federal Energy Regulatory Commission may require, after consultation with and due consideration given to the views of the Attorney General, to ensure that its pipeline is operated in accordance with the competitive principles set forth in section 5(f)(1).

/s/ H. P. Sieverding
H. P. Sieverding, Acting Manager
Date: August 14, 1979

Tenneco Inc.
hereby agrees to be bound by the foregoing.

/s/ F. J. Millette
F. J. Millette, Agent and Attorney-in-Fact

Date: August 13, 1979

cc: ☒ Geological Survey, USDI
Office of Pipeline Safety Operations, USDT

5/29/79



United States Department of the Interior

GEOLOGICAL SURVEY

434 IMPERIAL OFFICE BLDG., 3301 N CAUSEWAY BLVD

P O BOX 7944

METAIRIE, LOUISIANA 70010

TEL (504) 837-4720

RECEIVED
MAY 29 12 26 PM '79
BUREAU OF LAND MANAGEMENT
OUTER CONTINENTAL
SHELF OFFICE
NEW ORLEANS, LA
MAY 29 1979

In Reply Refer To: OS-5

R

Memorandum

To: Manager, Bureau of Land Management, 841 Hale Boggs Federal Building, 500 Camp Street, New Orleans, Louisiana 70130

From: Conservation Manager, Gulf of Mexico Region

Subject: Tennessee Gas Pipeline Company's Pipeline Right-of-Way Application, BLM OCS-G 4040, Reference 2883(210)

We have reviewed the safety features and design specifications for the subject Right-of-Way Application, dated May 11, 1979, in accordance with the MOU dated August 1, 1974. It is for the construction, maintenance, and operation of a 10 3/4-inch gas pipeline 8,878 feet in length from Tenneco's proposed Platform "B", High Island Block A-336, lease OCS-G 2424, to High Island Offshore System's Platform "A", High Island Block A-343, lease OCS-G 2741.

Based upon information submitted in the application, the design characteristics of this pipeline are calculated to be as follows:

<u>Pipeline Component</u>	<u>Maximum Allowable Operating Pressure/WP Ratings</u>
Submerged component	2,344 psig
Riser component	1,628 psig
Valves, flanges, fittings	1,440 psig

The hydrostatic pressure test with water will be at 2,160 psig for eight hours for the submerged component. The riser will be pre-installation-tested to a pressure of 2,160 psig for four hours. The ANSI 600 valves should not be subjected to a test-pressure differential greater than 1,440 psig. The ANSI 600 valves, flanges, and fittings should not be subjected to a body test greater than 2,175 psig.

Based on these calculations, we recommend that the maximum allowable operating pressure for this pipeline be 1,440 psig (which is the hydrostatic test pressure divided by 1.5) and that this pressure may be exceeded only when hydrostatically pressure-testing the pipeline.

The technical aspects of the proposed pipeline are acceptable in accordance with appropriate regulations and standards.

We would appreciate receiving a copy of the plat showing the location of the pipeline as installed.

Lowell L. Hammons
Acting Conservation Manager

RECEIVED
MAY 29 12 26 PM '79
BUR OF LAND MGMT.
OUTER CONTINENTAL
SHELF OFFICE
NEW ORLEANS, LA.

Memorandum

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT


IN REPLY REFER TO:
2883 (210)

To : Conservation Manager
Gulf of Mexico OCS Operations
FROM : Manager
New Orleans OCS Office
SUBJECT : Tenneco Inc.'s Pipeline Right-of-way Application (OCS-G 4040)

Date: May 18, 1979

In accordance with the memorandum of understanding between the Bureau of Land Management and U. S. Geological Survey signed August 1, 1974, the subject application is attached.

Please review the technical aspects of the proposed pipeline. If you have any questions regarding this matter, please contact Mr. Autry J. Britton of this office.



Attachments

1. Application dated May 11, 1979
2. Drawing No. TA-L2-F823X-1600-1, -1A, -1B,
and -1C, Revision 1

210/AJBritton/mhh/5-18-79

Tennessee Gas Pipeline

Division of Tenneco Inc

P.O. Drawer 53388
Lafayette, Louisiana 70501
(318) 233-7802



May 11, 1979

RECEIVED

MAY 14 3 28 PM '79

BUR OF LAND MGMT.
OUTER CONTINENTAL
SHELF OFFICE
NEW ORLEANS, LA.

Mr. John L. Rankin, Manager
Outer Continental Shelf Office
500 Camp Street, Suite 841
Hale Boggs Federal Building
New Orleans, Louisiana 70130

Re: Application - Right of Way for
10" Natural Gas Pipeline in
High Island Area, Gulf of Mexico
(H.I.O.S. A-336-B Line)

Dear Mr. Rankin:

Pursuant to Section 5 (c) of the Outer Continental Shelf Lands Act of August 7, 1953 (67 Stat.464), and the regulations contained in 43 CFR 2883, Tennessee Gas Pipeline Company, A Division of Tenneco Inc., is filing this application for a right of way 200 feet (200') in width for the purpose of constructing and maintaining a ten inch (10") natural gas pipeline in the High Island Area, Gulf of Mexico. Tennessee Gas Pipeline Company agrees that said right of way, if approved, will be subject to the terms and conditions of said regulations.

This pipeline will be used to gather and transport natural gas from Tenneco's "B" platform in Block A-336, High Island Area, in the Gulf of Mexico. The tentative construction dated is August 1, 1979, and tentative completion date is September 30, 1979.

As set forth in the April 1, 1976, guidelines as amended February 1, 1977, and April 21, 1977, the applicant agrees to furnish the following:

NEW ORLEANS OCS
FILE CODE 1.

Letter of Application, in duplicate.

ROUTE INITIAL
 MGR. 2.
 ASST. MGR.

Certified and Return Receipts with copies of letter of notification to the following lease and right of way holders:

MAY 14 1979

 P. LEGAL
 PAO
 EAD
 OPS
 STUDIES
 MGMT. SER.

- a. Gulf Oil Company - OCS-G 2424
- b. Tenneco Exploration Ltd. - OCS-G 2424
- c. High Island Offshore System - OCS-G 3302
- d. The Superior Oil Company - OCS-G 2741
- e. Exxon Corporation - OCS-G 2741
- f. Canadian Superior Oil (U.S.) Ltd. - OCS-G 2741
- g. Alminex U.S.A., Inc. - OCS-G 2741
- h. Natresco Incorporated - OCS-G 2741

TENNESSEE GAS PIPELINE COMPANY

Mr. John L. Rankin, Manager
Outer Continental Shelf Office
Page Two
H.I.O.S. A-336-B Line

3. Six (6) blue line prints of Drawing No. TA-L2-F823X-1600-1, TA-L2-F823X-1600-1A; TA-L2-F823X-1600-1B and TA-L2-F823X-1600-1C showing the location, profile and route of the proposed pipeline, Hi-Lo Censor locations and typical pipeline crossing detail.
4. Two (2) blue line prints of Drawing No. TA-L2-F823X-1600-2 showing the leases and pipeline rights of way.
5. Bury all pipelines to a minimum of 3 ft. of cover up to the 200 ft. contour. (This particular line is well below the 200 ft. contour).
6. Bury all sub-sea valves to a minimum of 1 ft. of cover regardless of water depth.
7. A hazard survey report of the proposed right of way route is attached in duplicate.
8. An archaeological survey report as stipulated in requirements is not required.
9. In accordance with the guidelines an As-Built map along with diving inspection reports will be provided within 90 days after completion of the pipeline.
10. Safety devices will be provided as set forth on attached schematic Drawing No. TA-L2-F823X-1600-1B.
11. Proper notification prior to construction and hydrostatic testing will be adhered to.
12. Any pipeline crossings will be in compliance with the guidelines as set forth.
13. Any breaks, leak failures or accidents will be reported as required.

In addition to the above information, applicant submits the following information:

1. Water depth along route of proposed pipeline and pipeline in relationship to natural bottom as set forth on attached drawing No. TA-L2-F823X-1600-1A.

TENNESSEE GAS PIPELINE COMPANY

Mr. John L. Rankin, Manager
Outer Continental Shelf Office
Page Three
H.I.O.S. A-336-B Line

2. The description of the pipe and coating is as follows:

a. Line Pipe

10.750" OD x .500" W.T. Gr B; Weight Bare - 54.74#/ft.
coated with 22 mils of heat cured epoxy or coal tar
enamel 6/32" thick, giving a specific gravity of
1.36 in salt water (64.0#/cu. ft.).

b. Riser Pipe

10.750" OD x .500" W.T. Gr B; Weight Bare - 54.74#/ft.
coated with 22 mils of heat cured epoxy or coal tar
enamel 6/32" thick. Specific gravity of 1.36 in salt
water (64.0#/cu. ft.).

c. Internal Coating

The analysis of the transported products will be
monitored and preventive measures such as pigging
and/or inhibiting will be employed as necessary.

3. Valves and Flanges

a. Below water valves and flanges will be A.N.S.I. 900
series with a rated working pressure of 2160# P.S.I.

b. Above water flanges and valves will be A.N.S.I. 600
series with a rated working pressure of 1440# P.S.I.

4. The specific gravity of the product being transported is
anticipated to be .60 (Air = 1.0), T = 60°F.

5. Weight, type and spacing of anodes to be used as corrosion
protection are shown on attached Drawing No. TA-L2-F823X-
1600-1B entitled "Schematic." The life expectancy of the
proposed pipeline is indefinite. The sacrificial anodes are
designed for 40 year life and are to be replaced as
necessary to extend life of pipeline.

6. The design of the proposed pipeline is in accordance with
'Minimum Federal Safety Standards (Department of Transportation)
Title 49, CFR, Part 192.'

TENNESSEE GAS PIPELINE RECEIVED

Mr. John L. Rankin, Manager
Outer Continental Shelf Office
Page Four
H.I.O.S. A-336-B Line

MAY 14 3 28 PM '79
BUR OF LAND MGMT.
OUTER CONTINENTAL
SHELF OFFICE
NEW ORLEANS, LA.

7. Maximum Allowable Operating Pressure (M.A.O.P.) = 1440# P.S.I.G.

Maximum Capacity = 28 MMCF/D

Maximum Operating Pressure (M.O.P.) is less than or equal to 1440# P.S.I.G.

Minimum Operating Pressure = 500# P.S.I.G.

A. Calculations

Formulas:

$$P = \frac{2st}{d}$$

$$M.A.O.P. = \frac{2st (F) (E) (T)}{d}$$

Whereas: P = 100% S.M.Y.S.

s = Specified Minimum Yield Strength

t = Nominal Wall Thickness in Inches

d = Nominal Outside Diameter in Inches

(F) = 0.50 for Riser Pipe

= 0.72 for Line Pipe

As per Title 49, CFR, Part 192.619

(E) = 1 - for seamless and DSA welded pipe

(T) = 1 - for temperature less than 250°F

a. Riser Pipe

$$\underline{10.750'' \text{ OD} \times .500'' \text{ W.T. Gr 'B'}}$$

$$P = \frac{2 \times .500 \times 35,000}{10.750} = 3,256\# \text{ P.S.I.G.}$$

(1) M.A.O.P. (Design)

$$M.A.O.P. = \frac{2 \times .500 \times 35,000 \times .50 \times 1 \times 1}{10.750} = 1,628\# \text{ P.S.I.G.}$$

(2) M.A.O.P. (Hydrostatic Test Pressure)

$$H.T.P. = P \times 90\%$$

$$= 3,256 \times .90 = 2,930\# \text{ P.S.I.G.}$$

H.T.P. will be 2,160# P.S.I.G. for 4 hrs.

$$M.A.O.P. = \frac{2160}{1.5} = 1,440\# \text{ P.S.I.G.}$$

TENNESSEE GAS PIPELINE COMPANY

Mr. John L. Rankin, Manager
Outer Continental Shelf Office
Page Five
H.I.O.S. A-336-B Line

$$(3) \text{ M.A.O.P.} = 1628\# \text{ P.S.I.G. (Design) or } 1440\# \text{ P.S.I.G. (H.T.P.)}$$

b. Line Pipe
10.750" x .500" W.T. Gr "B"

$$P = \frac{2 \times .500 \times 35,000}{10.750"} = 3,256\# \text{ P.S.I.G.}$$

(1) M.A.O.P. (Design)

$$\text{M.A.O.P.} = \frac{2 \times .500 \times 35,000 \times .72 \times 1 \times 1}{10.750} = 2344\# \text{ P.S.I.G.}$$

(2) M.A.O.P. (Hydrostatic Test Pressure)

$$\begin{aligned} \text{H.T.P.} &= P \times 90\% \\ &= 3256 \times .90 = 2930\# \text{ P.S.I.G.} \\ \text{H.T.P. will be } 2160 \text{ P.S.I.G. for 8 hrs.} \\ \text{M.A.O.P.} &= \frac{2160}{1.25} = 1728\# \text{ P.S.I.G.} \end{aligned}$$

$$(3) \text{ M.A.O.P.} = 2344\# \text{ P.S.I.G. (Design) or } 1728\# \text{ P.S.I.G. (H.T.P.)}$$

Since there are A.N.S.I. 600 series valves in the system, the M.A.O.P. therefore is restricted to 1440# P.S.I.G.

8. The producers equipment will be designed for 1440# P.S.I.G.
9. The 36" line that the proposed line will tie into is 36" OD x .625" W.T. Gr X-60 pipe.
10. An originally signed copy of Non-Discrimination in Employment Stipulations is enclosed in duplicate.
11. Company contact:

Mr. Reno G. Robertson, Division Civil Engineer
P. O. Drawer 53388, OCS
Lafayette, Louisiana 70505
318/233-7802

TENNESSEE GAS PIPELINE COMPANY

Mr. John L. Rankin, Manager
Outer Continental Shelf Office
Page Six
H.I.O.S. A-336-B Line

RECEIVED
MAY 14 3 28 PM '79

BUR OF LAND MGMT.
OUTER CONTINENTAL
SHELF OFFICE
NEW ORLEANS, LA.

12. Tennessee Gas Pipeline Company's Draft No. 25685 in the amount of \$20.00 of which \$10.00 covers the application fee and \$10.00 covers the first year's rental on 1.68 miles of right of way is also enclosed.

Please refer to your miscellaneous 014 file for a copy of a resolution approved by the Board of Directors authorizing the undersigned as Supervisor-Rights of Way of Tennessee Gas Pipeline Company, A Division of Tenneco Inc., to sign for and on behalf of the Company.

We trust the above information will enable you to expedite the issuance of the Decision approving said right of way.

Yours very truly,

TENNESSEE GAS PIPELINE COMPANY
A DIVISION OF TENNECO INC.



F. J. Millette, Supervisor
Rights of Way as
Agent and Attorney-in-Fact

Certified Mail - Return Receipt No. 197535

BEST AVAILABLE COPY

RECEIVED

NOTE: This form must be executed as an original. MAY 14 3 30 PM '79

BUR OF LAND MGMT.
OUTER CONTINENTAL
SHELF OFFICE
NEW ORLEANS, LA.


UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

NONDISCRIMINATION IN EMPLOYMENT

As a condition precedent to the approval of the granting of the subject pipeline right-of-way, the grantee Tennessee Gas Pipeline Company
A Division of Tenneco Inc.
hereby agrees and consents to the following stipulation which is to be incorporated into the application for said right-of-way.

During the performance of this contract the grantee agrees as follows:

During performance under this grant, the grantee shall fully comply with paragraphs (1) through (7) of section 202 of Executive Order 11246 as revised (reprinted in 41 CFR 60-1.4(a)), which are for the purpose of preventing discrimination against persons on the basis of the race, color, religion, sex or national origin. Paragraphs (1) through (7) of section 202 of Executive Order 11246 as amended are incorporated in this grant by reference.


Signature of Grantee

Date: May 11, 1979

HIGH ISLAND AREA



TENNECO
OCS-G-2424

RECEIVED
MAY 14 3 28 PM '79
BUR OF LAND MGMT.
OUTER CONTINENTAL
SHELL OFFICE
NEW ORLEANS, LA.

A-337

A-335

PROPOSED
TENNECO OIL COMPANY
BLK A-336B PLATFORM
HIGH ISLAND AREA

X = 3,686,415.25
Y = 135,251.07
LAT = 28°06'05.532"
LONG = 93°46'05.231"

EXIST H.I.O.S 36" PIPELINE

PROPOSED RIGHT-OF-WAY
FOR 10" T.G.P NATURAL GAS
PIPELINE

Y=134,640.00

EXXON, ET AL
OCS-G-2741

A-342

A-343

A-344

X = 3,678,000
Y = 130,000

H.I.O.S
BLK A-343A PLATFORM
HIGH ISLAND AREA
X = 3,694,528.97
Y = 131,646.72
LAT = 28°05'26.281"
LONG = 93°44'36.543"

X = 3,701,000
Y = 130,000

PLAN




STATE OF LOUISIANA
LARRY J. BROUSSARD
REG. NO. 14589
REGISTERED PROFESSIONAL CIVIL ENGINEER
LOUISIANA REGISTERED PROFESSIONAL CIVIL ENGINEER NO. 14589

THIS PIPELINE TO BE USED TO TRANSPORT
NATURAL GAS FROM OFFSHORE TEXAS TO
EXISTING SYSTEMS.
ALL BEARINGS SHOWN ARE LAMBERT.
PROPOSED WIDTH OF RIGHT-OF-WAY 200'.
TOTAL LENGTH OF PIPELINE 8,878.28 FEET =
1.68 MILES.

OFFICE COPY

I 4-24-79 REDRAWN - CHANGED ROUTE		GLD	CJB	TA-L2-F823X-1600-1A TA-L2-F823X-1600-1B TA-L2-F823X-1600-1C	PROFILE SCHEMATIC PIPELINE CROSSING DETAIL
NO	DATE	REVISION	REV	CKD	APR
DRAWN BY GLD DATE 4-24-79			Tennessee Gas Pipeline Company		
CHECKED BY CJB DATE "			Division of Tenneco Inc		
CORRECT BY DATE			Engineering Department Houston, Texas		
APPROVED BY DATE			APPROVED BY		
SCALE SHOWN C O			FOR CHIEF ENGINEER		
OCS-G 4040			APPLICATION PLAT FOR PROPOSED NATURAL GAS PIPELINE RIGHT-OF-WAY		
			Tennessee Gas Pipeline Co.		
			TA-L2-F823X-1600-1		




PROFILE

60 0 60
VERTICAL SCALE OF FEET

4000 0 4000
HORIZONTAL SCALE OF FEET

NO.	DATE	REVISION	REV.	CKD	APR	TA-L2-F823X-1600-1 TA-L2-F823X-1600-1B TA-L2-F823X-1600-1C	PLAN SCHEMATIC PIPELINE CROSSING DETAIL
1	4-25-79	REDRAWN - CHANGED ROUTE	GLD	CJB		DRAWING NO.	TITLE
DRAWN BY G.L.D. DATE 4-25-79						Tennessee Gas Pipeline Company	
CHECKED BY C.J.B. DATE "						Division of Tenneco Inc	
CORRECT BY DATE						Engineering Department Houston, Texas	
APPROVED BY DATE						APPROVED BY <i>[Signature]</i> FOR CHIEF ENGINEER	
SCALE SHOWN C O						Tennessee Gas Pipeline Co.	
APPLICATION PLAT FOR PROPOSED						TA-L2-F823X-1600-1A	
NATURAL GAS PIPELINE RIGHT-OF-WAY							

H.I.O.S.
HIGH ISLAND AREA
BLK. A-343A PLATFORM




10 750" O.D. x 500" W.T. GR. "B"
RISER PIPE

NOTE:


THE DESIGN CHARACTERISTICS OF THE PIPELINE ARE IN COMPLIANCE WITH D.O.T. REGULATIONS.

10 750" O.D. x 500" W.T. GR. "B"
RISER PIPE

HI-LO SENSORS



TENNECO OIL CO.
HIGH ISLAND AREA
BLK. A-336B PLATFORM






TA-L2-F823X-1600-1
TA-L2-F823X-1600-1A
TA-L2-F823X-1600-1C



PLAN
PROFILE
PIPELINE CROSSING DETAIL

1	4-26-79	REDRAWN - CHANGED ROUTE	GLD	CJB	DRAWING NO.	TITLE
NO.	DATE	REVISION	REV.	CKD	APR	REFERENCE DRAWINGS
DRAWN BY G.L.D. DATE 4-26-79 CHECKED BY C.J.B. DATE " CORRECT BY DATE APPROVED BY DATE SCALE SHOWN C.O.			Tennessee Gas Pipeline Company Division of Tenneco Inc. Engineering Department Houston, Texas			APPROVED BY FOR CHIEF ENGINEER
						Tennessee Gas Pipeline Co.
SCHEMATIC PROPOSED T.G.P. 10" HIGH ISLAND BLK. A-336B LINE HIGH ISLAND AREA GULF OF MEXICO			TA-L2-F823X-1600-1B			

BEST AVAILABLE COPY



TA-L2-F823X-I600-1B SCHEMATIC
 TA-L2-F823X-I600-1 PLAN
 TA-L2-F823X-I600-1A PROFILE

NO		DATE		REVISION		REV	CKD	APR	DRAWING NO		TITLE	
									REFERENCE DRAWINGS			
DRAWN BY G. L. D.		DATE 3-5-79		 Tennessee Gas Pipeline Company Engineering Department Houston, Texas				APPROVED BY		 FOR CHIEF ENGINEER		
CHECKED BY C. J. B.		DATE						Tennessee Gas Pipeline Co.				
CORRECT BY		DATE						TA-L2-F823X-I600-IC				
APPROVED BY		DATE										
SCALE NONE		C O		PROPOSED 10" NATURAL GAS PIPELINE TYPICAL PIPELINE CROSSING SEPARATION DETAIL HIGH ISLAND AREA, GULF OF MEXICO								

10³/₄ p/ Proposed Platform
Tennessee "B", HI A-336, G 242 4040
~~TO ASSTL W HIOS 36" HI A-343, G 241 (See OCS-G 3302)~~
~~TO HIOS Plat "A", HI A-343, G 2741~~
~~NAOP 1440~~

(1.68mi) PIPELINE APPLICATION CHECK LIST 8878.28 (1.68149mi) **BEST AVAILABLE COPY**

INSTRUCTIONS: Check the blank on the left if the statement is affirmative or correct data submitted. Mark N/A (not applicable) where appropriate. Place an X in the blank if the answer is no or if the data was not submitted. All blanks marked X must be rectified to a check (or qualified) before approval can be given for the pipeline. Enter data in the blanks on the right.

A. Verify the following general information:

I. SOP

- _____ a. Do the leases involved on the P/L application appear on the current Suspension of Production (SOP) Lease List?

II. POD

- _____ a. Is the pipeline presently covered by an approved Plan of Development (POD)? (Discuss ROU&E with Doug.) If yes, go to III. If No, go to 250.34. (Requires submittal to POD/P by operator to District.)

III. USGS Application

- _____ a. The applicant is a Federal lease holder and the pipeline is to be used for such purposes as:
- _____ 1. Moving production to a control point for gathering, treating, storing, or measuring.
 - _____ 2. Delivery of production to a point of sale.
 - _____ 3. Delivery of production to a pipeline operated by a transportation company.
 - _____ 4. Moving fluids in connection with lease operations, such as for injection purposes.
- _____ b. The pipeline is within the lease boundary owned by the operator (If yes, include 30 CFR 250.19(b) in approval.)
- _____ c. Pipeline is within contiguous lease boundaries. (If yes, include 30 CFR 250.19(b) in approval.)
- _____ d. Pipeline is within non-contiguous lease boundaries. (If yes, include 30 CFR 250.18(c) and 30 CFR 250.19(b) in approval.)
- _____ e. Lessee's "intent to cross" letter are received. (Wait 30 days for letters of objection. Only objections concerning interference with lease operations will be considered.)
- _____ f. Pursuant to Secretarial Order 2974 of April 30, 1975, check the following:

- ~~1. FWS notified _____.~~
- ~~2. FWS comment received _____.~~
- ~~3. BLM notified _____.~~
- ~~4. BLM comment received _____.~~
- ~~5. Environmental Impact Evaluations completed _____.~~
- ~~6. If related to new POD/P, date of POD/P approval _____.~~

IV. BLM Application

- ☒ a. The pipeline must be able to be subjected to common carrier provisions (i.e., no downstream production facilities or downstream pipelines which could not be subjected to common carrier provisions).

V. DOT Pipelines

- ☒ a. The pipelines are shoreward of the outlet flange at the first process facility (If yes, include 49 CFR 192 for gas P/L or 49 CFR 195 for oil P/L in approval).

VI. DOI Pipelines

- N/A a. Pipelines not covered by V above.

BEST AVAILABLE COPY

B. Verify that the information shown on the safety equipment schematic drawing contains the following:

- ☒ I. The pipeline leaving the platform receiving production from the platform is equipped with high and low pressure sensors located upstream of departing check valves to directly or indirectly shut-in the well or wells on the platform.
- ☒ N/A II. The pipeline delivering production to production facilities on the platform is equipped with an automatic fail close valve tied into the automatic and remote shut-in system.
- ☒ PRODUCTION III. The pipeline crossing the platform which does not deliver production to the platform, but which may or may not receive production from the platform, is equipped with high and low pressure sensors connected to an automatic fail close valve located in the upstream portion of the pipeline at the platform. In addition, the sensors are tied into either the platform's automatic and remote shut-in system or an independent remote shut-in system.
PLAT NON-PRODUCTION PLAT ∴ NOT APPLICABLE PER AGO 5/22/90
- ☒ IV. The pipeline boarding the platform is equipped with a check valve.
- ☒ V. The pipeline leaving the platform is equipped with a check valve.
- ☒ N/A VI. The pipeline pump is shown as well as its associated high and low pressure shut-in device.
- ☒ VII. If pipeline pilots are located on any process vessel, all flow restrictions (backpressure valves, chokes) downstream of pilots are indicated on the schematic.
- ☒ VIII. Pressure source is drawn into the schematic with the following:
- ☒ a. Source SEPARATOR.
- ☒ b. Maximum source pressure, psig 1440.
- ☒ IX. The rated working pressures of all separators, pumps, compressors, valves, flanges, and fittings upstream of and including the boarding automatic fail close valve are shown.

ANSI 600 1440

C. Verify that the location plat depicts the following:

- ☒ I. Location of P/L
- ☒ II. Length of P/L
- ☒ III. Size of P/L
- ☒ IV. Type of service
- ☒ V. Direction of flow

D. Verify that the information given on the submitted data sheet is complete; and calculate the $MAOP_{sc}$, $MAOP_{rc}$, $MAOP_{p/l}$.

I. General information for calculating $MAOP_{sc}$, $MAOP_{rc}$, etc.

- a. Size of P/L, inches 10.75
- b. Weight of P/L, lbs./ft. 54.74
- c. Grade of P/L B
- d. Wall thickness, inches 0.500
- e. Size of riser, inches 10.75
- f. Weight of riser, lbs./ft. 54.74
- g. Grade of riser ~~200~~ B
- h. Wall thickness of riser, inches 0.500
- i. Minimum WP rating of piping, fittings, valves, psig 1440
- j. Hydrostatic test pressure (HTP), psig Riser 2160 LINE 2160
- k. Hold time, hrs. 4 8
- l. Classification of P/L (oil or gas) gas

III. DOT Pipelines

a. IP @ SMYS for submerged pipeline = $\frac{2st}{D} = \frac{(2)(35000)(.5)}{10.75} = 3256$

b. (.72 x IP @ SMYS) for submerged pipeline = 2344 (MAOP_{sc})

c. IP @ SMYS for riser = $\frac{2st}{D} = \frac{(2)(35000)(.5)}{10.75}$

d. For oil P/L (.60 x IP @ SMYS) for riser = _____ (MAOP_{rc})

For gas P/L (.50 x IP @ SMYS) for riser = 1628

e. See Ii above 1440 (MAOP_{pfv})

✓ f. Are b, d, and e \geq MSP

1440 \geq 1440

NOTE: If not, a departure is necessary requiring redundant safety equipment.

A written request for a departure has been received and the redundant safety equipment is satisfactory.

g. Limit of Testing

N/A 1. For oil P/L:

Is $1.25 \text{ MSP} \leq \text{HTP} \leq .95 \text{ (IP @ SMYS for smaller IP of a and c above)}$

 \leq 2160 \leq

✓ 2. For gas P/L riser component:

Is $1.50 \text{ MSP} \leq \text{HTP of riser} \leq .95 \text{ (IP @ SMYS of c above)}$

2160 \leq 2160 \leq 3093

✓ 3. For gas P/L submerged component:

Is $1.25 \text{ MSP} \leq \text{HTP of submerged component} \leq .95 \text{ (IP @ SMYS of a above)}$

1800 \leq 2160 \leq 3093

NOTE: If not, inquire of the operator as to what he considers a limit of testing as a percentage of IP @ SMYS.

N/A Operator's answer _____ % of IP @ SMYS (for smaller IP)

h. MAOP_{p/l} based on HTP

- N/A 1. For oil P/L HTP/1.25 = _____
- ✓ 2. For gas P/L riser component ²¹⁶⁰ HTP/1.5 = 1440
of riser
- ✓ 3. For gas P/L submerged component ²¹⁶⁰ HTP/1.25 = 1728
of submerged
component

N/A i. For oil P/L Is HTP hold time \geq 24 hours

✓ For gas P/L Is HTP hold time \geq 8 hours

j. MAOP_{p/l} = the smallest of b, d, e, and h above

1440 (MAOP_{p/l})

k. Test pressure ANSI & API carbon steel RTJ & RF flanges and valves

2160 (From table 3.1 page 31 API RP 14E)

l. Is $k \geq$ HTP 2160 \geq 2175

NOTE: If not, add statement in approval letter to insure valves and flanges are not subjected to test pressure.

IV. Pipeline Receiving Production (Installed Prior to July 31, 1977)

	<u>Submerged Component</u>	<u>Riser</u>
a. Size, inches	_____	
b. Grade	_____	
c. Wall thickness, inches	_____	
d. Minimum working pressure of valves and flanges	_____	(MAOPpfv)
e. Date of last hydrostatic test	_____	
f. HTP, psig	_____	
g. Hold time, hours	_____	
h. MAOP based on HTP HTP/1.25	_____	
i. IP@SMYS for submerged P/L 2ST/D	_____	
j. (.72 X IP@SMYS) for submerged P/L	_____	(MAOPsc)
k. IP@SMYS for riser 2ST/D	_____	
l. (.60 X IP@SMYS) for riser	_____	(MAOPrc)
m. If the receiving P/L is a DOT gas P/L and has not been tested since July 1, 1971, then what is the MAOP to which the segment was subjected during the 5 years prior to July 1, 1976?	_____	
n. MAOP of receiving P/L — MAOP of proposed P/L — MAOP of proposed P/L	_____	_____

- E. Verify that the information given on the submitted data sheet is complete; and calculate the life expectancy of the pipelines corrosion protection ($LE_{p/1}$)

I. General Information for Calculating $LE_{p/1}$

✓ a. Type of corrosion protection (platform anodes, P/L anodes, or rectifiers)

N/A b. If platform anodes are used:

1. Type of anode _____

2. Weight of unit anode, lbs. _____

✓ c. If pipeline anodes are used:

1. Type of anode ZINC

2. Spacing interval, ft. 2959' separation - 50 # ea 2 groups 13 ea.

3. Weight of unit anode, lbs. 50

II. Calculated Life Expectancy of Corrosion Protection

N/A a. If platform anodes are used, are they considered adequate _____

✓ b. If pipeline anodes are used:

$$LE_{p/1} = 3.82 \times 10^4 \times W^0 / DIR? = \frac{3.82 \times 10^4 \times 13 \times 50}{10.75 \times 26 \times 4438.5} = 20.01$$


W^0 = weight of one anode, pounds =

D = outside diameter of pipe, inches

I = interval = length of pipe, feet ÷ total number of anodes 26

R = consumption rate, lbs./amp-yr.

✓ c. Is our calculated $LE_{p/1} \geq 20$ years



F. Verify that the information given on the submitted data sheet is complete; and calculate the specific gravity of the pipeline ($SG_{p/l}$)

- I. General Information pertaining to $SG_{p/l}$ *22 miles epoxy or*
- a. Description of pipelines protective coating *Coal Tar enamel 6/32"*
 - b. Description of risers protective coating _____
 - c. Description of pre-concrete coating _____
 - d. Density of concrete, lbs./cu. ft. _____
 - e. Thickness of concrete, inches _____
 - f. Thickness of asphalt/somastic _____
 - g. Gravity or density of products _____
- For gas 16 (air = 1.0)
- For oil/condensate _____ ° API, _____ (water = 1.0)
- h. Given $SG_{p/l}$ 1.36

II. $SG_{p/1}$

BEST AVAILABLE COPY

✓ a. Epoxy-coated pipelines:

$$SG_{p/1} = 2.865 \frac{W}{D^2} = 1.3571$$

W = weight of bare pipe, lbs./ft.

D = diameter of pipe, inches

N/A b. For weighted pipelines:

$$SG_{p/1} = \frac{d_c}{d} + \frac{k_2}{(T-k_1)^2} \left(\frac{W+P}{k_3} - \frac{d_c}{d} \right)$$

d_c = density of concrete, lbs./ft.³

d = density of fluid in which pipeline is submerged, lbs./ft.³

k_1, k_2, k_3 = coefficients from tables

T = thickness of concrete coating, inches

W = weight of bare pipe, lbs./ft.

P = weight of double enamel coat and felt wrap, or weight of asphaltmastic coating, lbs./ft.

$$SG_{p/1} = \underline{\hspace{2cm}}$$

✓ c. Is our calculated SG \approx operator's given SG

$$\underline{1.3571} \approx \underline{1.36}$$

NOTE: These values should be approximately the same. If not, resolve. If the SG is close to a value of 1, the pipeline is unacceptable and must be weighted with concrete or anchored securely to the bottom.

G. Verify the following general information:

I. Water Depth, ft. 240 (Max) 240 (Min)

II. Burial depth, ft. 0

III. Maximum Operating Pressure (MOP) 1440 (MIN) 500

IV. Capacity 1440 28 MMCF/D